

JORC RESOURCE TABLE JANUARY 2021

Deposit	Category	Cut-off (ppm U ₃ O ₈)	Tonnes (M)	U ₃ O ₈ (ppm)	U ₃ O ₈ (t)	U ₃ O ₈ (Mlb)	Resource Categories (Mlb U ₃ O ₈)		
							Measured	Indicated	Inferred
BASEMENT MINERALISATION									
Omahola Project - JORC 2004									
INCA Deposit ♦	Indicated	250	7.0	470	3,300	7.2	-	7.2	-
INCA Deposit ♦	Inferred	250	5.4	520	2,800	6.2	-	-	6.2
Ongolo Deposit #	Measured	250	7.7	395	3,000	6.7	6.7	-	-
Ongolo Deposit #	Indicated	250	9.5	372	3,500	7.8	-	7.8	-
Ongolo Deposit #	Inferred	250	12.4	387	4,800	10.6	-	-	10.6
MS7 Deposit #	Measured	250	4.4	441	2,000	4.3	4.3	-	-
MS7 Deposit #	Indicated	250	1.0	433	400	1	-	1	-
MS7 Deposit #	Inferred	250	1.3	449	600	1.3	-	-	1.3
Omahola Project Sub-Total			48.7	420	20,400	45.1	11.0	16.0	18.1
CALCRETE MINERALISATION Tumas 3 Deposit - JORC 2012									
Tumas 3 Deposits ♦	Indicated	100	43.1	299	12,900	28.4	-	28.4	-
	Inferred	100	39.6	245	9,700	21.4	-	-	21.4
Tumas 3 Deposits Total			82.7	273	22,600	49.8			
Tumas 1, 1 East & 2 Project – JORC 2012									
Tumas 1 & 2 Deposit ♦	Indicated	100	54.1	203	11,000	24.2	-	24.2	-
Tumas 1 & 2 Deposit ♦	Inferred	100	54.0	250	13,500	29.8	-	-	29.8
Tumas 1 & 2 Project Total			108.1	226	24,500	54.0			
Sub-Total of Tumas 1, 2 and 3			190.8	247	47,100	103.8			
Tubas Red Sand Project - JORC 2012									
Tubas Sand Deposit #	Indicated	100	10.0	187	1,900	4.1	-	4.1	-
Tubas Sand Deposit #	Inferred	100	24.0	163	3,900	8.6	-	-	8.6
Tubas Red Sand Project Total			34.0	170	5,800	12.7			
Tubas Calcrete Resource - JORC 2004									
Tubas Calcrete Deposi	Inferred	100	7.4	374	2,800	6.1	-	-	6.1
Tubas Calcrete Total			7.4	374	2,800	6.1			
Aussinanis Project - JORC 2004									
Aussinanis Deposit ♦	Indicated	150	5.6	222	1,200	2.7	-	2.7	-
Aussinanis Deposit ♦	Inferred	150	29.0	240	7,000	15.3	-	-	15.3
Aussinanis Project Total			34.6	237	8,200	18.0			
Calcrete Projects Sub-Total			266.8	232	62,100	140.6	-	59.4	81.2
GRAND TOTAL RESOURCES			315.5	261	82,500	185.7	11.0	75.4	99.3

Notes:

Figures have been rounded and totals may reflect small rounding errors.

XRF chemical analysis unless annotated otherwise.

♦ eU₃O₈ - equivalent uranium grade as determined by downhole gamma logging.

Combined XRF Fusion Chemical Assays and eU₃O₈ values.

Where eU₃O₈ values are reported it relates to values attained from radiometrically logging boreholes.

Gamma probes were calibrated at Pelindaba, South Africa in 2007. Recent calibrations were carried out at the Langer Heinrich Mine calibration facility in July 2018 and September 2019.

During drilling, probes are checked daily against standard source.